

Cumulus Linux NOS installation with Ansible

Created by:

Ron Wilhelmson

ron.wilhelmson@deltaww.com

Version:

Draft 1

Introduction

The process to remotely configure a switch with Cumulus Linux NOS with Ansible will be covered in this document. The following configuration tasks will be covered:

1. Installing Cumulus Linux NOS on a switch running ONIE
2. Installing Cumulus license on a switch running Cumulus Linux NOS
3. Re-installing or upgrading a switch with Cumulus Linux NOS

The following items and access will be required:

1. Binary installation file for Cumulus
2. Valid license file for Cumulus
3. Control server: Linux Ubuntu system with Ansible installed (Ubuntu 16.04.04 verified)
4. HTTP server: Server accessible via http:// URL for installation of binary and license files (can be run on control server)
5. Target Switch: Agema – AG7648
6. Console access to the switch will be helpful to see changes as they are run
7. Switch, control system, and http server must be on same network

Pre-install connectivity and Setup

Network and Systems required


The basic systems required for building and running Ansible playbooks consist of the following:

Control Server – Linux server that runs Ansible and contains playbooks.

Target Switch – Switch that is to be configured running ONIE and may be many.

Web Server – HTTP location where update, license, and install files are located.

Console Terminal – PC with console connection to switch and telnet to control server.



Network Diagram

Note: Please reference [Getting Started with Ansible](#) for additional details on system, switch, and server setups.

Configure Ansible on Control server:


You can configure Ansible (Ubuntu) via the PPA with the following commands:

```
$ sudo apt-get update
$ sudo apt-get install software-properties-common
$ sudo apt-add-repository ppa:ansible/ansible
$ sudo apt-get update
$ sudo apt-get install ansible
```

Verify Ansible is installed with:

```
$ ansible --version
```

Configuration should look something like this



```
root@DPR-LABVM-01:/etc/ansible# ansible --version
ansible 2.5.0
  config file = /etc/ansible/ansible.cfg
  configured module search path = [u'/root/.ansible/plugins/modules', u'/usr/share/ansible/plugins/modules']
  ansible python module location = /usr/lib/python2.7/dist-packages/ansible
  executable location = /usr/bin/ansible
  python version = 2.7.12 (default, Dec  4 2017, 14:50:18) [GCC 5.4.0 20160609]
root@DPR-LABVM-01:/etc/ansible#
```

Switch ready state:

The target switch should be installed with the management port on the back of the switch connected to the local network and an IP assigned to the switch. A console connection should also be defined so that switch status can be monitored (see below). The console terminal should have the following prompt if ONIE is installed correctly:

```
ONIE: #
```

Note: ONIE release verified for this installation is 20170416-onie-recovery-x86_64-delta_ag7648-r0.iso

If ONIE is in discovery mode it will try to look for NOS installers in predefined locations. To stop this you can use the command:

```
ONIE: # onie-discovery-stop
```

Create HTTP server:

HTTP server can be a stand-alone web server that you can place files on or you can create a simple http server on your control server. To do this execute the following in a directory to keep binary, config, and license files such as “install” directory:

```
$ mkdir /root/cumulus
$ cd /root/cumulus
$ python2 -m SimpleHTTPServer 80 &
```

Place your Cumulus binary installation file and license file via ftp/sftp/tftp/scp/etc in the working directory. It should be visible by a browser on the local network at URL:

`http://[control server IP/Name]/`

You should see similar files when connected to this URL with a browser:

```
cumulus-linux-3.5.0-bcm-amd64.bin
cumulus_license.txt
```

Console terminal:

Configure the console terminal connection to the switch as follows:

1. Connect the console port of the switch to a PC. Most switches come with a RJ45 console port. Use a RJ45-to-serial cable or an RJ45-to- USB cable to connect to a PC.
2. Use a terminal application; such as “Tera Term” to terminal connect. Configure the console port with these settings:
 - 115200 baud
 - No flow control
 - stop bit
 - No parity bits
 - 8 data bits
3. Connect MGMT port of the switch to the same sub-net as terminal station

Ansible and Playbooks

Ansible is configured to work within a defined structure with dependencies on configuration file, hosts file, playbooks, and scripts. These are defined on the control server. For this guide the following network configurations are being used:

Control server assigned IP: 10.62.10.22 (hostname: DPR-LABVM-01)

HTTP server assigned IP: 10.62.10.22 (SimpleHTTPServer defined on control server)

Target switch assigned IP: 10.62.10.34

The ansible directory to work from can be created in any location on the control server. For this guide we are using the /etc/ansible directory and running as root. Non root accounts can be used as well but should have sudo access in order to run most commands.

Reguried files and execution:

ansible.cfg

definition and configuration file - using default config file for these playbooks

hosts

definition and configuration file - target switch and other systems defined in hosts file

roi.cfg

variable definition file - used for dependencies in roi.sh script

roi.sh

script for ssh command - called from Ansible for remote-onie-install.yml playbook

remote-onie-install.yml

YAML playbook executed by Ansible for install on switch running ONIE only

cumulus-install.yml

YAML playbook executed by Ansible for re-installing/upgrade of cumulus NOS

cumulus-lic-install.yml

YAML playbook executed by Ansible to install cumulus license file on switch

Directory structure, root user, cumulus user, and permissions:

```
root@DPR-LABVM-01:/etc/ansible# ls -al
total 64
drwxr-xr-x  3 root root  4096 Apr 15 23:45 .
drwxr-xr-x 99 root root  4096 Apr  7 12:29 ..
-rw-r--r--  1 root root 19342 Apr 15 23:23 ansible.cfg
-rw-r--r--  1 root root   646 Apr 15 23:23 cumulus-install.yml
-rw-r--r--  1 root root   477 Apr 15 23:23 cumulus-lic-install.yml
-rw-r--r--  1 root root   431 Apr 15 23:23 hosts
-rw-r--r--  1 root root  4284 Apr 15 23:45 Readme.md
-rw-r--r--  1 root root   126 Apr 15 23:23 remote-onie-install.yml
-rw-r--r--  1 root root   395 Apr 15 23:23 roi.cfg
-rwxr-xr-x  1 root root   708 Apr 15 23:23 roi.sh
root@DPR-LABVM-01:/etc/ansible#
```

Ansible commands to execute playbooks:

1. Install Cumulus NOS on switch running ONIE:

```
ansible-playbook remote-onie-install.yml --ask-pass
```

Playbook contains the following:

```
---
```

```
- hosts: localhost
  become: yes
  tasks:
    - name: Execute script
      command: '/bin/bash /etc/ansible/roi.sh'
```

The roi.sh script contains the following:

```
#!/bin/bash

# Copyright (C) 2018 Ron Wilhelmson <ron.wilhelmson@deltaww.com>
#
#

##
## remote-onie-install
##
## History: 12APR2018 Ron.Wilhelmson Initial Creation

# Dependencies: roi.cfg in same directory

# Set environment variables from roi.cfg for switch and server names/IPs
source ./roi.cfg

echo ""
echo "Target switch set to: $target_switch"
echo ""
echo "HTTP server set to: $http_server"
echo ""

echo "Sending install command to switch"

/usr/bin/ssh -a -l root $target_switch /bin/onie-nos-install
http://"$http_server"/cumulus-linux-3.5.0-bcm-amd64.bin

echo "Waiting for onie to download and install"
```

```
sleep 60

echo "Rebooting switch"

/usr/bin/ssh -l root $target_switch /sbin/reboot
```

The roi.cfg file contains the following:

```
# Copyright (C) 2018 Ron Wilhelmsen <ron.wilhelmsen@deltaww.com>
#
#

##
## remote-onie-install variable definitions
##
## History: 12APR2018 Ron.Wilhelmsen Initial Creation

# Reliancies: roi.sh

# target_switch is the switch that NOS is being installed on

target_switch=10.62.10.37

# http_server is the URL server where the NOS bin and license files are
located

http_server=10.62.10.22
```

Playbook execution and output:

```
root@DPR-LABVM-01:/etc/ansible# ansible-playbook remote-onie-install.yml --
ask-pass
SSH password:
```

```
PLAY [localhost]
*****
*****
```

```
TASK [Gathering Facts]
*****
*****
```

```
ok: [localhost]
```

```
TASK [Execute script]
*****
*****
```

```
The authenticity of host '10.62.10.34 (10.62.10.34)' can't be established.
RSA key fingerprint is SHA256:gqcwYNeppYieB0SnoypbqyW9i5dNfNakWxZEndHLY3o.
Are you sure you want to continue connecting (yes/no)? yes
10.62.10.34 - - [16/Apr/2018 00:36:02] "GET /cumulus-linux-3.5.0-bcm-
amd64.bin HTTP/1.1" 200 -
10.62.10.34 - - [16/Apr/2018 00:36:13] code 404, message File not found
10.62.10.34 - - [16/Apr/2018 00:36:13] "GET /cumulus-linux-3.5.0-bcm-
amd64.bin.preseed HTTP/1.1" 404 -
10.62.10.34 - - [16/Apr/2018 00:36:13] code 404, message File not found
10.62.10.34 - - [16/Apr/2018 00:36:13] "GET /cumulus-linux-3.5.0-bcm-
amd64.bin.ztp HTTP/1.1" 404 -
changed: [localhost]
```

PLAY RECAP


```
*****
*****
```

```
localhost : ok=2 changed=1 unreachable=0 failed=0
```

```
root@DPR-LABVM-01:/etc/ansible#
```


The nos-install utility attempts to download .preseed and .ztp files with the .bin image but in this case they are not being used and therefore get a “code 404, message File not found” which is normal in this case.

The switch console will display the following output:




```
COM4 - Tera Term VT
File Edit Setup Control Window Help
Stopping: discover... done.
ONIE: Executing installer: http://10.62.10.22/cumulus-linux-3.5.0-bcm-amd64.bin
Verifying image checksum ...OK.
Preparing image archive ... OK.
Verifying image architecture ...OK.
Verifying system ram ...OK.
Setting up installer ...Info: The full install log is located at /tmp/ei_runlog.XXCUptkS
OK.
Please reboot to start installing OS.
```


The switch will automatically reboot and install update screens will be displayed as follows:



Once the install completes the console will show the cumulus login prompt:



2. Re-install/Upgrade Cumulus NOS on switch running Cumulus NOS:

```
ansible-playbook cumulus-install.yml -k -K
```

cumulus-install.yml contains the following:

```
- hosts: switches
  connection: ssh
  remote_user: cumulus
  become: yes
  gather_facts: yes

vars:
  http_server: 10.62.10.22
  install_file: http://{{ http_server }}/cumulus-linux-3.5.0-bcm-
amd64.bin

tasks:
  - name: onie-nos-install Cumulus Linux NOS
    become-method: sudo
    shell: 'onie-install -f -a -i {{ install_file }}'
    tags: onie_nos_install
    notify:
      - snooze

  - name: reboot switch
    become-method: sudo
    command: 'reboot -f'
    notify:
      - wait for switch to come back up
```

handlers:

- name: snooze
local_action:
 module: wait_for
 host=switches
 port=22
 delay=20
 timeout=300
 state=started
- name: wait for switch to come back up
local_action: wait_for host=switches port=22 delay=20
 state=started
become: false

Playbook execution and output:

```
root@DPR-LABVM-01:/etc/ansible# ansible-playbook cumulus-install.yml  
-k -K
```

SSH password:

SUDO password[defaults to SSH password]:

[WARNING]: Ignoring invalid attribute: become-method

PLAY [switches]

TASK [Gathering Facts]

ok: [10.62.10.34]

TASK [onie-nos-install Cumulus Linux NOS]

10.62.10.34 - - [16/Apr/2018 04:19:39] "GET /cumulus-linux-3.5.0-bcm-amd64.bin HTTP/1.1" 200 -
changed: [10.62.10.34]

TASK [reboot switch]

PLAY RECAP

localhost : ok=2 changed=1 unreachable=0
failed=0

```
root@DPR-LABVM-01:/etc/ansible#
```

Console screen output:

```
COM4 - Tera Term VT
File Edit Setup Control Window Help
Loading Linux 4.1.0-cl-6-amd64 ...
Loading initial ramdisk ...
[ OK ] 0.070291 PCI: MMCONFIG has no entries
[ OK ] 0.085953 PCI: MMCONFIG has no entries
[ OK ] 2.326165 I8042: No controller found
Loading, please wait...
Scanning for Btrfs filesystems
Welcome to Cumulus Linux!
Expecting device dev-ttyS0.device...
[ OK ] Reached target Remote File Systems (Pre).
[ OK ] Set up automount Arbitrary Executable File Formats F...utomount Point.
[ OK ] Reached target Swap.
Expecting device dev-disk-by\x2duuid-1599d898\x2d079...fced.device...
[ OK ] Created slice Root Slice.
[ OK ] Created slice User and Session Slice.
[ OK ] Listening on /dev/initctl Compatibility Named Pipe.
[ OK ] Listening on Delayed Shutdown Socket.
[ OK ] Listening on Journal Socket (/dev/log).
[ OK ] Listening on LVM2 metadata daemon socket.
[ OK ] Listening on Device-mapper event daemon FIFOs.
[ OK ] Listening on udev Control Socket.
[ OK ] Listening on udev Kernel Socket.
[ OK ] Listening on Journal Socket.
[ OK ] Created slice System Slice.
Starting Increase datagram queue length...
Mounting Huge Pages File System...
Mounting POSIX Message Queue File System...
Starting Create list of required static device nodes...rrent kernel...
[ OK ] Created slice system-serial\x2dgetty.slice.

COM4 - Tera Term VT
File Edit Setup Control Window Help
[ OK ] Started /etc/rc.local Compatibility.
[ OK ] Started Permit User Sessions.
[ OK ] Started Initialize hardware monitoring sensors.
[ OK ] Started System Logging Service.
[ OK ] Started watchdog keepalive daemon.
Starting Machine Check Exception Logging Daemon...
[ OK ] Started Machine Check Exception Logging Daemon.
Starting Cumulus Linux System Monitoring Daemon...
[ OK ] Started Cumulus Linux System Monitoring Daemon.
Starting Cumulus Linux LED Manager Daemon...
[ OK ] Started Cumulus Linux LED Manager Daemon.
Starting Cumulus Linux Fan Control Daemon...
[ OK ] Started Cumulus Linux Fan Control Daemon.
Starting Cumulus Linux aclinit...
[ OK ] Started MSTP Daemon...
Starting MSTP bridge configuration...
Starting Cumulus Linux ZTP init and state capture...
Starting Cumulus Linux switch port setup...
[ OK ] Started A high performance web server and a reverse proxy server.
[ OK ] Started Login Service.
[ OK ] Started Cumulus Linux switch port setup.
Starting Cumulus Linux Fast Interface Shutdown...
[ OK ] Started Cumulus Linux Fast Interface Shutdown.
[ OK ] Started Cumulus Linux ZTP init and state capture.
Starting Daemon for generating UUIDs...
[ OK ] Started Daemon for generating UUIDs.
[ OK ] Started MSTP bridge configuration.
[ OK ] Started Cumulus Linux aclinit.
Starting ifupdown2 networking initialization...

COM4 - Tera Term VT
File Edit Setup Control Window Help
[ OK ] Reached target Network is Online.
Starting LLDP daemon...
[ OK ] Started NTP - Network Time Protocol daemon...
Starting Prescriptive Topology Manager (PTM) Daemon...
[ OK ] Started Prescriptive Topology Manager (PTM) Daemon...
Starting LSB: start and stop ptpd...
Starting (null)...
Starting LSB: Launch atftpd server...
Starting Cumulus Linux Multi-Chassis LACP Bonding Daemon...
Starting Cumulus Linux ZTP...
[ OK ] Started Cumulus Linux ZTP.
Starting OpenBSD Secure Shell server...
[ OK ] Started OpenBSD Secure Shell server.
Starting Serial Getty on ttyS0...
[ OK ] Started Serial Getty on ttyS0.
[ OK ] Reached target Login Prompts.
[ OK ] Started LLDP daemon.
[ OK ] Started LSB: start and stop ptpd.
[ OK ] Started LSB: Launch atftpd server.
[ OK ] Started Cumulus Linux Multi-Chassis LACP Bonding Daemon.
[ OK ] Started (null).
[ OK ] Reached target Multi-User System.
Starting Bootlog Service...
Starting Update UTMP about System Runlevel Changes...
[ OK ] Started Update UTMP about System Runlevel Changes.
[ OK ] Started Bootlog Service.
Debian GNU/Linux 8 cumulus ttyS0
cumulus login: 
```

3. Install Cumulus license file:

```
ansible-playbook cumulus-lic-install.yml --ask-sudo-pass
```

cumulus-lic-install.yml contains the following:

```
- hosts: switches
  connection: ssh
  remote_user: cumulus
  become: yes
  gather_facts: yes

  vars:
    http_server: 10.62.10.22
    license_file: http://{{ http_server }}/cumulus-linux-3.5.0-bcm-
amd64.bin

  tasks:

    - name: Download and install license for Cumulus Linux NOS
      become-method: sudo
      shell: 'cl-license -i {{ license_file }}'
      tags: cl-install

    - name: restart switchd service
      become-method: sudo
      shell: 'systemctl restart switchd.service'
      tags: restart-switchd
```

Note 1: sudo password for default cumulus user on cumulus NOS is:
CumulusLinux!

Note 2: ONIE root user password is: <none> enter return

Note 3: -vvv and -vvvv are sometimes useful as they extend the
level of verbose reporting through execution

Then the ssh-copy-id should be executed again to update the key entry:

```
root@DPR-LABVM-01:/etc/ansible# ssh-copy-id cumulus@10.62.10.34
/usr/bin/ssh-copy-id: INFO: Source of key(s) to be installed:
"/root/.ssh/id_rsa.pub"
The authenticity of host '10.62.10.34 (10.62.10.34)' can't be established.
ECDSA key fingerprint is
SHA256:jxfw26hjERJ0NxURlRfj70redK/tQTSdq90gp2bXDjc.
Are you sure you want to continue connecting (yes/no)? yes
/usr/bin/ssh-copy-id: INFO: attempting to log in with the new key(s), to
filter out any that are already installed
/usr/bin/ssh-copy-id: INFO: 1 key(s) remain to be installed -- if you are
prompted now it is to install the new keys
cumulus@10.62.10.34's password:
```

```
Number of key(s) added: 1
```

Now try logging into the machine, with: "ssh 'cumulus@10.62.10.34'"
and check to make sure that only the key(s) you wanted were added.

```
root@DPR-LABVM-01:/etc/ansible#
```

Example Playbooks and Projects:

The following git repository has example playbooks created for this guide and other applications that may be useful:

<https://github.com/DeltaProducts/Getting-Started-with-Ansible>

References:

Ansible User Guide

http://docs.ansible.com/ansible/devel/user_guide/intro_getting_started.html

Ansible Installation Guide

http://docs.ansible.com/ansible/latest/installation_guide/intro_installation.html

Ansible ansible-playbook Guide:

<https://docs.ansible.com/ansible/2.4/ansible-playbook.html>

Ansible Commands

http://docs.ansible.com/ansible/latest/modules/list_of_commands_modules.html

Ansible Modules

http://docs.ansible.com/ansible/latest/modules/list_of_all_modules.html

Tera Term Guide

<https://ttssh2.osdn.jp/index.html.en>

Open Network Install Environment (ONIE) Installation Guide

<https://github.com/DeltaProducts/SolutionCenter/blob/master/ONIE%20recovery%20from%20bootable%20USB.pdf>

Apache Web Server Setup Guide

<https://www.digitalocean.com/community/tutorials/how-to-install-the-apache-web-server-on-ubuntu-16-04>